

743-5

Majestic COAL WINDOWS

UNDERGROUND
GARBAGE RECEIVERS

Building Specialties



Manufactured by
THE MAJESTIC COMPANY
HUNTINGTON, INDIANA

[BLANK PAGE]



CCA

Majestic


COAL WINDOWS

UNDERGROUND GARBAGE RECEIVERS


Building Specialties

TABLE OF CONTENTS

| | Pages |
|--|-------|
| Foundation Coal Windows..... | 2-5 |
| Grade Line Coal Chutes..... | 6 |
| Store Coal Chutes..... | 7 |
| Complete Dimensions of all Coal Windows..... | 8 |
| Underground Garbage Receivers..... | 9-13 |
| Apartment Garbage Receivers..... | 14 |
| Built-In Garbage Receivers..... | 14 |
| All Metal Flower Boxes..... | 15 |
| Milk and Package Receivers..... | 16-17 |
| Fireplace Dampers..... | 18-19 |
| Rubbish Burners..... | 20 |
| Fireplace Ash Dumps..... | 21 |
| Flue Clean Out Doors..... | 21 |
| Ash Pit Doors..... | 21 |
| Manhole Doors..... | 21 |
| Cast Iron Flue Thimbles..... | 22 |
| Cistern Rings and Covers..... | 22 |
| Cellar Wall Grates..... | 22 |
| Porch Column Bases..... | 22 |
| Duplex Registers..... | 23 |
| Furnaces..... | 24 |



Majestic Factories at Huntington, Indiana

**GUARANTEED BREAK PROOF**

The illustration shows the detailed construction of No. M101 steel door type Majestic Coal Window as installed in building and open for delivery of coal.



Why Majestic Coal Windows

Lead in Quality and Value

Majestic Coal Windows are rapidly becoming "standard equipment" with home builders, architects, contractors, realtors and speculative builders. They save their initial cost in the protection they give the building, and enhance property value by their permanence, sightliness and convenience. Majestic Coal Windows are doing away with the old, short-lived frame windows and by their superiority of design and construction have won universal preference over ordinary metal coal windows.

Finest Quality Construction

Majestic Coal Windows are constructed of heavy electro-galvanized pressed steel, Keystone Copper Steel, and Certified Malleable Iron, reinforced at points of strain. They are built for permanent service—to stand up unmarred and undamaged under the heaviest conditions of usage. Backed by twenty years experience in building quality coal chutes.

Break Proof, Rust Proof Doors

The doors of Majestic Coal Windows are of heavy, pressed steel, electro-galvanized. In addition to being break-proof, the electro galvanizing process makes them rust proof as well. When raised, the door holds itself open automatically, thus protecting the building above the opening when coal is being deposited in bin.

Break Proof Frames

Frames of all types are of Certified Malleable Iron, so designed as to set perfectly in the masonry without any installation difficulties. Frame and door fit snugly, making the window completely weather-proof.

Break Proof Hinges

Hinges are of Certified Malleable Iron, making breakage at this point a practical impossibility. The hinges are flat with support on each side of the hinge pin. Neat, and inconspicuous, eliminating the necessity of cutting water table to provide hinge clearance.

Reinforced Bodies

Bodies and hoppers are heavily reinforced at points of strain. Angle iron reinforcement allows masonry to be laid directly on body without use of lintel. All bodies and hoppers are of Keystone Copper Steel.

Burglar Proof Automatic Locks

The new Majestic automatic locks are unfailing—burglar proof and trouble proof. Unlatch from the inside only, by a chain which may be extended to any part of the basement or house. The lock drops shut automatically when the door is closed.


Prevent This/



The ordinary basement window soon looks like the one above when used as a coal window. Wall, sash and frame battered, broken and disfigured. The Majestic Coal Window eliminates this.





And This/



The door, frame or hinges of the cast iron coal window frequently break under the heavy impact of coal as it is delivered. The Majestic Coal Window eliminates this—because it is break proof.

The Mark of a Modern Home



Sizes of Steel Door Styles
MAJESTIC COAL WINDOWS

| No. | Style | Rough Wall Opening | | | Shipping Weight |
|-----------|-------|--------------------|------|------|-----------------|
| | | Wide | High | Deep | |
| M101..... | B | 23" | 17" | 12" | 51 |
| M101..... | D | 23" | 17" | 12" | 40 |
| M203..... | B | 32" | 22" | 17" | 105 |
| M203..... | D | 32" | 22" | 17" | 87 |
| M500..... | | 23" | 17" | 9" | 35 |
| M520..... | | 32" | 22" | 12" | 71 |

(Style B is with Hopper—Style D without Hopper.)

Steel Door Styles

Majestic Coal Window No. M101 (Style B) is the finest and most complete coal window made. It has break-proof door of heavy, pressed steel, electro-galvanized to prevent rust. Frame and hinges are of break proof Certified Malleable Iron and body is Keystone Copper Steel with twelve inch sloping bottom. Angle iron reinforcement at top to carry masonry. Hopper to prevent scattering of coal. Style D is the same without the hopper. No. M203 Majestic is exactly the same as No. M101 except that it is larger in size.


No. M500 Majestic differs from No. M101 only in that it has nine inch straight bottom body and comes without hopper or chain to latch. It is of the same quality materials and represents an exceptional value. No. M520 is the same as No. M500 but larger in size.



Glass Panel Styles

Majestic Glass Panel Style No. M10 is sometimes preferred for dark basements. It has three lights of $\frac{1}{4}$ inch wire glass reinforced by two perpendicular metal strips to prevent breakage in shipment or installation. Glass is protected by steel shield when door is open. Heavy, pressed steel door, electro-galvanized, rust proof. Certified Malleable Iron frame. Hinges are of Certified Malleable Iron, flat and with double support. Body is Keystone Copper Steel with 12 inch sloping bottom. New automatic, burglar proof lock operated by inside chain. Style A with hopper and Style C without hopper.



No. M20 duplicates No. M10 in larger size. No. M600 is the same as No. M10 but has 9 inch straight bottom body without hopper or lock chain. No. M620 is larger than No. M600, but the same otherwise



Sizes of Glass Panel Styles
MAJESTIC COAL WINDOWS

| No. | Style | Rough Wall Opening | | | Shipping Weight |
|-----------|-------|--------------------|------|------|-----------------|
| | | Wide | High | Deep | |
| M10..... | A | 23" | 17" | 12" | 60 |
| M10..... | C | 23" | 17" | 12" | 50 |
| M20..... | A | 32" | 22" | 17" | 119 |
| M20..... | C | 32" | 22" | 17" | 100 |
| M600..... | | 23" | 17" | 9" | 42 |
| M620..... | | 32" | 22" | 12" | 86 |

(Style A is with Hopper—Style C without Hopper.)



SIZES OF

MAJESTIC GRADE LINE CHUTES

| No. | Door Opening | Rough Wall Opening | | Shipping Weight |
|----------|-------------------|--------------------|------|-----------------|
| | | Wide | High | |
| M16..... | 23 1/4" x 18 1/4" | 25" | 25" | 135 |
| M18..... | 29" x 24" | 31" | 31" | 200 |

GradeLineChutes

Majestic Grade Line Chutes, Nos. M16 and M18, are adapted for use where the foundation line is extremely low as in low set or terraced homes, apartments, stores or office buildings. When opened, the door swings up to form part of the hopper and to protect the building from flying lumps of coal. The frame is of Certified Malleable Iron, with solid brass hinge pins. Door is of heavy rolled, diamond surfaced steel—break proof. The Keystone Copper Steel body is reinforced with heavy angle iron. The frame is provided with water drainage groove under edge of door.


Nos. M16 and M18 are of identical construction but M18 is larger, as shown in the dimension chart.



Store Coal Chutes


Majestic Store Coal Chutes, Nos. M12 and M15 are made for use in stores and office buildings where the first floor is level with the sidewalk or alley. These store chutes take the place of the dangerous sidewalk coal hole and make it unnecessary to file a bond for the protection of pedestrians. Frame and hinges of these chutes are of Certified Malleable Iron. The door is of heavy pressed electro-galvanized steel—break proof and rust proof. Majestic Store Coal Chutes can be supplied, on special order, with duplex body so that coal can be deposited either under sidewalk or in basement.

Nos. M12 and M15 are the same except in size, the No. M15 being larger. Either size is supplied with or without hopper as desired.




Sizes of
MAJESTIC STORE CHUTES

| No. | Door Opening | Rough Wall Opening | | Shipping Weight |
|----------|------------------------|---------------------|---------------------|-----------------|
| | | Above Grade | Below Grade | |
| M12..... | 21"x15" | 23x16 $\frac{3}{4}$ | 23x25 | 105 |
| M15..... | 29"x19 $\frac{1}{4}$ " | 31x21 $\frac{1}{2}$ | 31x24 $\frac{1}{2}$ | 151 |



FOUNDATION COAL WINDOW



GRADE LINE COAL CHUTE

Complete Dimensions of Majestic Coal Windows and Coal Chutes

FOUNDATION COAL WINDOWS


| Style | A | B | C | D | E | F | G |
|-----------|--------|----|--------|--------|--------|--------|--------|
| M101..... | 24 1/8 | 12 | 18 1/4 | 21 3/4 | 12 1/2 | 18 1/8 | 15 1/2 |
| M203..... | 33 | 17 | 24 3/4 | 29 1/2 | 17 1/2 | 23 1/2 | 20 1/2 |
| M500..... | 24 1/8 | 9 | 15 1/2 | 21 3/4 | 9 | 18 1/8 | 15 1/2 |
| M520..... | 33 | 12 | 20 1/2 | 29 1/2 | 12 | 23 1/2 | 20 1/2 |
| M10..... | 24 1/8 | 12 | 18 1/4 | 21 3/4 | 12 1/2 | 18 1/8 | 15 1/2 |
| M20..... | 33 | 17 | 24 3/4 | 29 1/2 | 17 1/2 | 23 1/2 | 20 1/2 |
| M600..... | 24 1/8 | 9 | 15 1/2 | 21 3/4 | 9 | 18 1/8 | 15 1/2 |
| M620..... | 33 | 12 | 20 1/2 | 29 1/2 | 12 | 23 1/2 | 20 1/2 |

GRADE LINE COAL CHUTES

| Style | A | B | C | D | E | F | G | H | I | J |
|--------|--------|----|----------|--------|--------|--------|----|--------|--------|---|
| M16... | 26 | 21 | 4 15 1/2 | 24 1/2 | 24 1/4 | 36 1/2 | 19 | 16 3/4 | 19 1/4 | |
| M18... | 31 3/4 | 27 | 4 17 | 31 | 31 | 45 | 24 | 19 1/2 | 25 1/4 | |

STORE COAL CHUTES


| Style | A | B | C | D | E | F | G | H | I | J |
|------------|--------|--------|--------|--------|--------|----|--------|--------|--------|---|
| M12 25 | 11 1/2 | 26 3/8 | 15 1/4 | 23 | 19 1/2 | 13 | 15 1/2 | 17 | 18 | |
| M15 33 1/2 | 11 1/2 | 30 | 16 | 30 7/8 | 19 1/2 | 13 | 15 1/2 | 21 1/4 | 22 1/2 | |



STORE COAL CHUTE



Get Rid of This /



Put Your Garbage Can Underground

Out of Sight

Fly Proof

Odorless


Convenient

Dog Proof

Sanitary

The Following Pages Tell You How






*Section through Ground
showing Receiver Buried*

Step on Foot-Trip and Lid Raises

*Garbage Easily Deposited and as Easily Removed
Convenient--Sanitary*



FAR MORE CONVENIENT.



PLAIN CAN

Thousands of Majestic Underground Garbage Receivers in service in the best homes all over the country attest the growing realization of the need for this sanitary, convenient and unobtrusive means of garbage disposal. The unpleasantness of the old-time unsightly and insanitary "garbage can" is done away with by the Majestic Underground Garbage Receiver. It puts the garbage out of sight and out of reach of flies and prowling dogs.


The Majestic is quickly installed in any convenient spot—near the kitchen door if desired. The lid is opened by a slight pressure of the

Comes Complete

The Majestic Underground comes complete with can. specify which type can is heavy Majestic can or the Corrugated.

| No. | Capacity |
|-----|----------|
| 5 | al. |
| 8 | al. |
| 12 | 1 al. |
| 15 | 1 al. |
| 20 | 2 al. |

Approved by Good Housekeeping by Modern Price Testing



SIGHTLY AND SANITARY

Complete With Can

and Garbage Receiver
can. When ordering
is wanted—the plain
the extra heavy Witt

foot on the trip. Garbage is dropped into the can and the foot pressure on the trip released, the lid snapping tightly shut so that no odor can escape. When the can is full it is easily lifted out as shown in the illustration.


Top, consisting of ring, lid and foot lever, is of cast iron. The shell is of Keystone Copper Steel. Can is galvanized and comes in the plain heavy type or the extra heavy Witt Corrugated. The entire Receiver is treated to prevent rust or deterioration. Supplied in five sizes ranging from 5 to 20 gallons in capacity. Comes complete with can.




WITT CAN

| | Shipping Weight | |
|--|-----------------|----------|
| | Plain Can | Witt Can |
| | 31 | 35 |
| | 48 | 53 |
| | 54 | 60 |
| | 60 | 66 |
| | 92 | 99 |

Housekeeping Institute and
Testing Laboratory.




No. 9A Apartment Garbage Receiver



No. 3A Apartment Garbage Receiver



Inside View No. 5K Built-In Garbage Receiver



Outside View No. 5K Built-In Garbage Receiver

Apartment and Built-in Garbage Receivers

THE No. 3A MAJESTIC APARTMENT GARBAGE RECEIVER consists of a heavy cast iron frame and door—galvanized iron body which recesses in the wall—and a garbage can of 3 gallons capacity. The garbage pail sets on a cast iron shelf which is fastened to the door. When the door is opened the can is ready to receive the garbage—see illustration above. Two heavy cast iron ventilators 4" by 2 1/4" are supplied with this receiver.

The No. 9A MAJESTIC APARTMENT GARBAGE RECEIVER has a front casting only, with a steel body that is recessed in the wall to receive the garbage can. The front is provided with double doors below the garbage door for removing the garbage pail—see illustration above.

The front of the No. 5K Majestic Built-in Garbage Receiver opens into the Kitchen where the garbage is deposited—see illustration. The back opens to some accessible place outside the building, where the garbage is removed. The doors fit closely and lock with a refrigerator type latch. The body is adjustable for 8" and 12" walls. For narrow walls casings may be used inside and outside.

Sizes of Apartment and Built-In Garbage Receivers

| No. | Can Capacity | Wall Openings | | Shipping Weight |
|---------|--------------|---------------|------|-----------------|
| | | Wide | High | |
| 3A..... | 3 gal. | 14 1/2" | 12" | 36 |
| 9A..... | 9 gal. | 19" | 29" | 110 |
| 5K..... | 12 gal. | 19" | 29" | 176 |



Majestic All-Metal Flower Boxes


Constructed entirely of metal, the Majestic outlasts several wooden flower boxes. Hence, Majestic Flower Boxes actually cost you less—and they always look better.

The Majestic is so constructed that it gives all kinds of plant life the same opportunity to flourish as in nature. The double bottom forms a reservoir which is filled with water through the tube at the end of the box. The water is taken up by the plants, and goes directly to the roots, through the holes in the inside bottom.


A hole punched in one end of the box provides adequate ventilation. The inside bottom and watering tube are removable, which makes it easy to clean the box when replanting. Made of heavy galvanized iron, reinforced at the top by a $\frac{3}{4}$ " bead and pressed iron corners. All joints are securely soldered—and the entire box is finished in green waterproof enamel.

Sizes of
MAJESTIC FLOWER BOXES

| No. | Overall Dimensions | | |
|----------|--------------------|------|------|
| | Long | Wide | High |
| 24..... | 24" | 10" | 8" |
| 30..... | 30" | 10" | 8" |
| 36..... | 36" | 10" | 8" |
| 12..... | 12" | 12" | 8" |
| 14..... | 14" | 14" | 8" |
| 17..... | 17" | 17" | 9" |
| 12A..... | 12" | 12" | 10" |
| 14A..... | 14" | 14" | 12" |
| 17A..... | 17" | 17" | 15" |




SQUARE TYPE FOR PORCH POSTS,
PEDESTALS OR SUSPENSION



Section Removed
to Show Construction


The illustration above shows the scientific construction of the Majestic All-Metal Flower Box which gives all kinds of plant life the same opportunity to flourish as in nature.



OUTSIDE VIEW, OPEN



OUTSIDE VIEW, CLOSED




OUTSIDE VIEW—RECEIVING MILK

Majestic Milk and

The Majestic Milk and Package Receiver makes it possible to receive milk, groceries and other parcels without going outside or opening a door of the house. Two cast iron frames and doors connected by an adjustable steel body are installed in the wall of the kitchen. An arrangement of the burglar proof latch allows the doors to be reversed at the time of installation—either can be installed inside or outside to open either to the right or to the left by simply changing latch from one door to the other.

Both of the doors can be unlocked from the inside only. The delivery man deposits the articles in the Receiver from the outside. When he closes the outside door it locks automatically and can not be opened again until the latch is released by an extended chain on the inside, making the Receiver ready for further deliveries. The Majestic Receiver is inconspicuous, occupies no needed space and gives protection against weather, annoyance, theft and intrusion.


Installation of the Majestic Milk and Package Receiver may be made even in a frame house with walls as narrow as 6 inches. Such an installation gives suffi-



INSIDE VIEW, OPEN

Package Receivers

cient space to hold six quart bottles of milk or parcels of equivalent size. The depth and capacity may be increased by the use of casings inside and out and extending the body of the Receiver to full length. The Majestic Milk and Package Receiver is the mark of a completely modern home.



Sectional View




INSIDE VIEW, CLOSED

Supplied in Two Sizes

Majestic Milk and Package Receiver No. 1 has a body adjustable from 5 to 8 inches. Majestic Receiver No. 2 is adjustable from 8 to 12 inches. Wall opening 12 inches high and 14 inches wide is required. Bodies of special depths can be supplied at a slight additional cost.


| No. | For Wall Thickness | Shipping Weight |
|--------|-----------------------|-----------------|
| 1..... | 5 inches to 8 inches | 45 |
| 2..... | 8 inches to 14 inches | 49 |




INSIDE VIEW—REMOVING MILK




Majestic Fireplace Dampers



Majestic Fireplace Damper as installed in Fireplace.



End View showing friction type of control.



End view showing ratchet type of Control.

A fireplace can be a source of comfort or a nuisance—depending upon its construction and its damper. It is impossible for a fireplace to function well without a properly designed damper. Adequate flue area and smoke chamber are also essential to satisfactory operation.

The Majestic Damper is scientifically designed, simple in construction, easy to operate and *gives perfect draft* control. The Majestic throat is theoretically and practically correct due to the built-in lintel, which assures the correct height of damper throat above finished opening—also correct position of damper. Installed in any reasonably well built fireplace, it insures absolute satisfaction. Smoking in the room is eliminated by the Majestic Damper.

The making of the lintel integral with the frame of the damper makes it absolutely assured that the distance from the top of the opening of the fireplace to the top of the throat is correct—and this is the most important dimension of the whole fireplace. It also makes it necessary to place the damper forward in the fireplace, thus leaving room for a smoke shelf behind the throat.



Give Perfect Draft Control


The valve of the Majestic is hinged at the back. This aids the smoke shelf in turning the down-draft back up the chimney. Many fireplaces are unsatisfactory due to the absence of this damper feature. Ease of operation in the Majestic Damper is accomplished by the trouble proof friction principle for opening and closing the door or valve. The operating mechanism (a lever fastened to the door) is moved forward or backward by the touch of a poker. The door always stays in position and allows the most minute adjustments to comply with varying wind and weather conditions.

The sides of the Majestic Damper are made at an angle of 15° with the lintel and rest on the splayed fire-brick sides of the fire box. The length of the damper is measured in steps of four inches, the lintel having exactly enough bearing for the size of opening corresponding to the size of damper. When the damper is used with intermediate sizes of openings the bearing is more than enough.

With the simple poker control there are no knobs or handles to protrude through the front of the fireplace. The Majestic Type X, however, is supplied for those who prefer the handle or knob control. Both types are illustrated on the preceding page.

Installation of the Majestic Fireplace Damper is very easy. An inexperienced workman, by following the instructions supplied with each Majestic Damper, can build a perfect fireplace—one which will give the greatest heat with economy of fuel, and which will not smoke.

| Width Finished Opening | Height Finished Opening | Depth of Firebox | Height Rough Opening | Size of Flue Required | Majestic Damper Number |
|------------------------------|-------------------------------|------------------------|----------------------------|-----------------------------|------------------------------|
| 26" | 28" | 16" | 40" | 8"x 8" | 26 |
| 30" | 30" | 17" | 43" | 8"x 8" | 30 |
| 34" | 30" | 18" | 43" | 8"x12" | 34 |
| 38" | 31" | 19" | 46" | 8"x12" | 38 |
| 42" | 31" | 20" | 46" | 12"x12" | 42 |
| 46" | 32" | 21" | 46" | 12"x12" | 46 |
| 50" | 32" | 22" | 46" | 12"x16" | 50 |
| 54" | 32" | 23" | 46" | 12"x16" | 54 |



Section through fireplace showing location of Majestic Fireplace Damper.





Majestic Rubbish Burners



Vertical Model No. 33

The Majestic No. 33 Rubbish Burner will easily outlast two or three of the cheaper wire burners. It is constructed of twelve gauge steel expanded metal, with wrought iron legs and pressed steel cover. Provided with steel bottom which can be dumped without removing burner. Pressed steel top is chained and can be easily opened with stick while fire is burning. This burner is extremely durable throughout. It is supplied in one size—No. 33—18 inches in diameter and 24 inches deep.


Driveway and Lawn Model No. 35



Majestic also offers an entirely new type of Rubbish Burner—one which will not leave a pile of ashes or require an inconvenient or unsightly location for operation. With the new Majestic Rubbish Burner papers and other refuse can be burned right on the lawn or driveway without leaving a trace or injuring the grass.

The New Majestic consists of a square basket of heavy wire with perforated sheet metal ends. The basket may be rotated at a touch, is self cleaning and will burn all waste paper—even heavy magazines and similar rubbish—completely. The ash falls into the pan which is emptied when necessary. Large hinged door makes filling an easy matter.


This burner need be kept in sight only when in actual use. It may be stored in the garage or basement and brought out when needed. May be used on lawn, driveway or street. It is safe, clean and durable. It is made in one household size, No. 35—basket 17 inches square and pan 24 inches long. Its capacity will surprise you.



Majestic Ash Pit Doors

These doors are placed in the base of chimney flue so that ashes or soot may be removed. Majestic Ash Pit Doors are built to fit closely and securely. Construction is of heavy cast iron. Latch is simple and effective. Hinges are sturdy and smooth in action. Doors are made in two sizes as indicated below.



| Size | Frame | Door | Shipping Weight |
|--------------|-------|------|-----------------|
| 12"x15"..... | Cast | Cast | 23 |
| 15"x15"..... | Cast | Cast | 35 |



Majestic Manhole Doors

Made from 10 gauge copper steel. Well hinged. Supplied in three sizes.

| Size | Frame | Door | Shipping Weight |
|---------|-------|---------------------|-----------------|
| 18"x24" | Cast | 10 Ga. Copper Steel | 44 |
| 24"x30" | Cast | 10 Ga. Copper Steel | 60 |
| 24"x36" | Cast | 10 Ga. Copper Steel | 65 |



Left: Front view door closed.

Above: Rear view showing anchor irons extended.

Majestic Flue Clean Outs

The Majestic Flue Clean Out is made of the highest quality cast iron, hand fitted. It has a malleable iron turn key and latch that locks the door securely. Its anchor irons fold flat. Made in four sizes. Twelve of each size to a crate. The No. 1012 is also ample in size for an ash pit door.

| No. | Size | Shipping Weight Dozen |
|-----------|---------|-----------------------|
| 88..... | 8"x 8" | 85 |
| 810..... | 10"x 8" | 92 |
| 812..... | 12"x 8" | 125 |
| 1012..... | 12"x10" | 180 |



Majestic Fireplace Ash Dumps

The Majestic Ash Dump has the lid permanently hinged to the frame so that it cannot fall out. The ash dump is essential in any fireplace. It keeps dust and odors from the room and permits ashes from fire to drop to base of chimney.


| No. | Outside | Inside | Shipping Wt. Doz. |
|---------|---------|--------|-------------------|
| 6..... | 8"x 8" | 6"x6" | 45 |
| 8..... | 10"x10" | 8"x8" | 60 |
| 9..... | 6"x 9" | 4"x7" | 38 |
| 10..... | 7"x10" | 5"x8" | 46 |



Majestic Cistern Ring and Cover

Majestic Cistern Ring and Cover is used for cisterns, cess pools and other underground receptacles. Consists of heavy circular cast iron rim and cover. Cover is flush and has drop handle to facilitate easy lifting. Made in four sizes, ranging from 18 inches to 24 inches inside diameter.


| Inside Diameter | Outside Diameter | Weight Each, lbs. |
|-----------------|------------------|-------------------|
| 18"..... | 24" | 45 |
| 20"..... | 26" | 56 |
| 22"..... | 29" | 70 |
| 24"..... | 31" | 88 |



Majestic Porch Column Bases

Majestic Porch Column Bases form the ideal base for wooden columns. They protect the base of the Column from rot and decay, and from marring and damage to the paint. Made of heavy cast iron, designed to support the column firmly. Made in eight sizes.


| Size | Weight | Size | Weight |
|-------------------|--------|----------------|--------|
| 8"x 8"x2"..... | 9 | 16"x16"x2 1/2" | 43 |
| 10"x10"x2"..... | 15 | 18"x18"x2 3/4" | 54 |
| 12"x12"x2 1/8"... | 22 | 20"x20"x2 3/4" | 74 |
| 14"x14"x2 1/4"... | 30 | 24"x24"x3 1/8" | 115 |



Majestic Cast Iron Flue Thimble

The Majestic Flue Thimble is installed in the masonry of the chimney to carry the furnace smoke pipe. The pipe fits snugly inside the collar of the Flue Thimble and may be easily removed for cleaning.


| Size of Smoke Collars | Size Overall | Weight Each |
|-----------------------|--------------|-------------|
| 5"..... | 5 1/2" | 3 1/2 |
| 6"..... | 6 1/2" | 4 3/4 |
| 7"..... | 7 1/2" | 5 |
| 8"..... | 8 1/2" | 5 1/4 |
| 9"..... | 9 1/2" | 6 1/4 |
| 10"..... | 10 1/2" | 9 |




Majestic Cellar Wall Grate

Majestic Cellar Wall Grates provide a means of safe ventilation for basements. They fit securely and are neat in appearance. Made of heavy cast iron. Eight sizes.

| Size | Weight, Each | Size | Wt. Each, lbs. |
|-----------|--------------|---------|----------------|
| 4"x 8"... | 2 | 8"x12" | 5 |
| 6"x 8"... | 3 | 8"x16" | 5 1/2 |
| 6"x12"... | 4 | 10"x12" | 6 1/2 |
| 8"x 8"... | 4 | 10"x16" | 10 1/2 |



Majestic Duplex Registers



The Majestic Duplex Register is one of the greatest improvements ever made in warm air heating. Installed with any warm air furnace it assures better circulation and greater heating efficiency. For small homes where a single register system is sufficient it offers many additional advantages. For example, the Majestic Duplex Register occupies about one-half less floor space than a floor level register of equal capacity. It locates against the wall, out of the way—harmonizes with your room furnishings—and does not become a receptacle for dust and dirt from sweepings.

For larger homes, where a single register system is not sufficient, it is a simple matter to take a run of pipe from the furnace to your bathroom or other out of the way point—or two Duplex Registers may be used to advantage. Thus, with the Majestic Duplex Registers you can have a heating system with all the advantage of both pipe and pipeless systems without the disadvantages of either. Catalog giving complete details and descriptions of Majestic Duplex Registers will be supplied on request.



Majestic Quality Furnaces



MAJESTIC DOWN DRAFT FURNACE



MAJESTIC STANDARD FURNACE

Majestic Quality Furnaces give the greatest possible heating efficiency with the minimum fuel consumption. Constant improvement throughout Majestic's 30 years of furnace building has brought them to a point of superiority that is outstanding in the industry.

Majestic furnaces will give many more years of service than the ordinary cast or steel types, and considering the great saving in operation the initial cost becomes of little importance. All Majestics embody the best points of other furnaces, combined with exclusive Majestic features of design and construction.

Majestics have gas and dust proof joints, extra large feed and ash pit doors, removable grates, and extra wide and deep radiators to insure good draft and provide additional heating surface. A complete furnace catalog containing detailed information and comprehensive illustrations will be mailed you on request.



MAJESTIC 1200 SERIES

[BLANK PAGE]



CCA

